

1 050787

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,303 -00-00
NW NW NE SEC. 17, T 18 S, R 28 W/K
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Walker Well # 1

Operator: D. G. Hansen Trust

County Lane 99.68

Name & Address P. O. Box 187

Well Total Depth 3067 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Co., Inc. License Number 5783

Address 340 Broadway Plaza, 105 S. Broadway, Wichita, KS 67202

Company to plug at: Hour: 8:30 pm Day: 24 Month: March Year: 19 86

Plugging proposal received from Carl McGuire

(company name) Galloway (phone) 316-263-1793

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2109-2140! Elevation 2750'

1st plug at 1400' with 80 sx cement

2nd plug at 300' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pm Day: 24 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Lost drill collars on bottom to Top of fish at 2684'

1st plug at 1400' with 80 sx cement, 2nd plug at 300' with 50 sx cement, 3rd & 4th plugs -

solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to

circulate rat hole with 15 sx cement.

Also they lost 340' of wash pipe in the hole at 1926 to 1660'

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

INVOICED
APR 1 1986

Signed Richard W. Lacey
(TECHNICIAN)

DATE

INV. No. 13209

3-24

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 3/17/86
 month day year

API Number 15- 101-21,303-60-00

OPERATOR: License # 5285
 Name D.G. Hansen Trust
 Address Box 187
 City/State/Zip Logan, KS 67646
 Contact Person Dane G. Bales
 Phone (913) 689-4816

NW. NW. NE Sec. 17 Twp. 18 S. Rg 28 East
4950' West
2310' Ft. from South Line of Section
 Ft. from East Line of Section
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5783
 Name Galloway Drilling Co., Inc.
 City/State Wichita, KS 67202
 Well Drilled For: Well Class: Type Equipment:
 Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet
 County Lane
 Lease Name Walker Well # 1
 Ground surface elevation 1275.0 TOPD feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no
 Surface pipe by Alternate: 1 2 3
 Depth to bottom of fresh water 150'
 Depth to bottom of usable water 1100' - 1350'
 Surface pipe planned to be set 250'
 Projected Total Depth 4550' feet
 Formation Mississippi

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 3/17/86 Signature of Operator or Agent Jay H. Galloway Title President

For KCC Use:
 Conductor Pipe Required 9-17-86 feet; Minimum Surface Pipe Required 200 feet per Alt. 2
 This Authorization Expires 3-19-86 Approved By [Signature]

3-19-86 called Galloway - Tapped to Susie about 2nd plug - Told her to be sure have rig set plug @ 1400 in D+A. S.D. PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>2075</u>	feet depth with <u>50</u>	sxs of <u>cement</u>
2nd plug @ <u>900 - 1400</u>	feet depth with <u>80</u>	sxs of <u>cement</u>
3rd plug @ <u>394 - 300</u>	feet depth with <u>50</u>	sxs of <u>cement</u>
4th plug @ <u>40</u>	feet depth with <u>10</u>	sxs of <u>cement, 1 sack hulls</u>
5th plug @	feet depth with	sxs of
(2) Rathole with <u>15</u>	sxs	(b) Mousehole with sxs

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.

PUSHER Carl Mcquire
 TD 3068 FORMATION
 SURFACE PIPE 8 1/8" @ 252
 ANHYDRITE 2109 ELEVATION 2750
 STARTING TIME & DATE 3-24-86 8:30 PM
 COMPLETION TIME & DATE 3-24-86 11:00 PM
 1st PLUG @ 1400 FT. W/ 80 SX
 2nd PLUG @ 300 FT. W/ 50 SX
 3rd PLUG @ 40-0 FT. W/ 10 SX
 4th PLUG @ FT. W/ SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ SX
 WATER WELL PLUGGED W/ SX
 CEMENT COMPANY Alley
 TECHNICIAN Lacey
 Lost drill collars on bottom to top of fish 2684
 Lost Wash pipe at 926 + 1666
 1st plug @ 1400 w/ 80 300 w/ 50 40 w/ 10

MAR 31 1985

CONSERVATION DIVISION
 Wichita, Kansas