

6-7-88

To: 1 051062
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21-304-00-00
NW NW NE, SEC. 17, T 18 S, R 28 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5285
Operator: The Dane G. Hansen Trust
Name & Address P.O. Box 187
Logan, KS 67646

4950 feet from S section line
2310 feet from E section line
Lease Name Walker "A" Well # 1
County _____ Lane _____ : 149.01
Well Total Depth 4585 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 7 Month: 6 Year: 19 88

Plugging proposal received from Bill Fulls
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4400' PBD 4370' Perfs at 4323-27'
1st plug sand back to 4275' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:45 a. Day: 7 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released
8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 200 psi. JUN - 8 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2040' of 5 1/2" casing.
(if additional description is necessary, use BACK of this report)
CONSERVATION DIVISION
Wichita, Kansas

Observe this plugging.

Signed Richard M. Lucas
(TECHNICIAN) *SMA*

INVOICED
DATE 6-30-88
INV. NO. 21149