

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21492-00-00  
Spot: NESENE Sec/Twnshp/Rge: 13-18S-28W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: BOLTZ Well Number: 1-13  
County: LANE Total Vertical Depth: 4650 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4453 WITH 160 SX CMT  
Surface Casing Size: 8.625 feet: 250 WITH 160 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2003 10:40 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: TED FUCHS Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING WITH 300# HULLS & 391 SX CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS WITH 50 SX CMT. CUR OFF PIPE STRINGS BELOW PLOW DEPTH & RESTORE LOCATION.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 07/01/2003 11:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4453'. PERFS AT 4334-4337'. DV TOOL @ 2100'. CEMENTED WITH 400 SX CMT. CMT CIRCULATED TO SURFACE. PUMPED 300# HULLS & 60 SX CMT FOR BOTTOM PLUG. PUMPED 330 SX CMT. CASING PRESSURED TO 1100#. SHUT IN WITH 800#. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300# & HELD.

RECEIVED  
JUL 16 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael J. Maier  
(TECHNICIAN)

Form C-2/3