

To: 1090635
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-21,653 -00-00
SE NW SE, SEC. 8 T 18 S, R 28 WXX
1650 feet from S section line
1650 feet from E section line

12-14

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Yost Well # 2

Operator: Viking Resources, Inc.

County Lane

Name & Address 105 S. Broadway, Ste. 1040

Well Total Depth 4592 149.24 feet

Wichita, KS 67202-4224

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 9 a.m. Day: 14 Month: 12 Year: 1995

Plugging proposal received from Jim Devlin

(company name) Viking Resources, Inc. (phone) 316-262-2502

logs: 4 1/2" at 4591' w/200 sx cement, DV at 2139' w/390 sx cement, PBD 4552', Perfs at 4249-51, 4223-25'

1st plug pump down 4 1/2" casing with hulls and cement to surface.

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10 a.m. Day: 14 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 2 sx hulls, 25 sx cement, 20 sx gel, with 220 sx cement. Maximum pressure 2000 psi and shut in 500 psi. Backside.OK Cement in connections.

RECEIVED KANSAS CORPORATION COMMISSION

DEC 20 1995

CONSERVATION DIVISION WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. (If additional description is necessary, use BACK of this form.)

INVOICED

Signed [Signature] (TECHNICIAN)

DATE JAN 09 1996

INV. NO. 44471

12-14 FEB 29 1996