

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,758-00-00 *R*

NW, Sec. 2, T 18 S, R 28 W1/4

2310 feet from N1/4 section line

2310 feet from W1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name NILES Well # 1

Operator: CHIEF DRILLING Co, INC  
Name & Address 905 CENTURY PLAZA  
WICHITA, KS 67202

County LANE

Well Total Depth 4560 feet \$148.<sup>20</sup>

Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_

Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Strata Drilling Co License Number 6188

Address Box 355, GREAT BEND, KS 67530

Company to plug at: Hour: 3:00 p.m. Day: 14 Month: FEB Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Heward Cain

(company name) Strata (phone) 316-653-2463

were: to use 50/50 Pozmix, 4% gel-3% C.C. & spot 1<sup>st</sup> plug @  
2070' w/50 sz; 2<sup>nd</sup> plug @ 1035' w/50 sz; 3<sup>rd</sup>  
plug @ 390' w/40 sz; 4<sup>th</sup> plug @ 40' w/solid bridge  
of hells & 8 5/8 plug; 5<sup>th</sup> 40'-0' w/10 sz. Circ. 10" dia  
in rat hole & mouse hole.

Signed R Barluttan  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:00 p.m. Day: 14 Month: FEB Year: 1983

ACTUAL PLUGGING REPORT plugged as ordered.  
Cementing by Allied.

Remarks: 8 5/8" set w/225 sz OF 60/40 Pozmix, 2% gel-3% CC  
Anhydrite top @ 2059', base @ 2095'

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were \_\_\_\_\_ as hereon stated  
and that I (~~did~~ / did not) observe this plugging.

Signed R Barluttan  
(TECHNICIAN)

INVOICED

DATE MAR 25 1983

INV. NO. 3715-W