

1030112

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,933 -00-00
75E NE
NW NE, Sec. 24, T. 16 S, R. 27 W/EX

330 feet from N/S section line

1575 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6390

Lease Name McBee Well # 1

Operator: McDonald-Wallace Petroleum Co.
Name & 509 Landmark Square
Address Wichita, KS 67202

County Lane

Well Total Depth 4583 feet 148.94

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 12:15 am Day: 23 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO LeRoy Barnes

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2060' with 50 sx cement

2nd plug at 1080' with 50 sx cement

3rd plug at 360' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement

Signed Steve Demont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00 am Day: 23 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2060' with 50 sx cement, 2nd plug at 1080'

with 50 sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole
with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing

RECEIVED
STATE CORPORATION COMMISSION

FEB 29 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~did~~ / did not observe this plugging.

Signed Steve Demont
(TECHNICIAN)

INVOICED
DATE 3-8-84
INV. NO. 0601
2-23

FORM CP-2/3
Rev. 9-82