

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,762-~~0080~~

N/4, Sec. 24, T 16 S, R 27 W/4

2310 feet from N/4 section line

660 feet from ~~N/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name MCBEE Well # 1

Operator: SABRE Exploration, INC.
Name & Address 105 S. BROADWAY, STE. 130
WICHITA, KS 67202

County LANE

Well Total Depth 4590 feet 149.18

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 377

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor WHEATSTATE OILFIELD SERV. License Number 5149-87

Address Box 947, Pratt, KS 67124

Company to plug at: Hour: 11:30 AM, Day: 9 Month: MARCH Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Steve Fellers

(company name) Wheatstate (phone) _____

were: 50/50 Poz mix, 4% ogel-3% cc - 1st plug @ 5100'
w/50 sz; 2nd @ 1050' w/50 sz; 3rd @ 420'
w/40 sz; 4th @ 40' w/solid bridge of hulls &
8 5/8 plug and 10 sz; 5th circ. 15 sz in
rat hole.

Signed R. B. Arlinton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:35 PM Day: 8 Month: FEB Year: 19 83

ACTUAL PLUGGING REPORT Plugged as ordered.
Cementing by Sun.

Remarks: Anhydrite top @ 2080

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1983
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 4-11-83
INV. NO. 3945-4

Signed R. B. Arlinton
(TECHNICIAN)



Oilfield Services, Inc.

15-101-20762-00-00

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS' WELL LOG

McBee
 NE/4 24-16-27
 Lane County, Kansas
 Commenced : 2-23-83
 Completed : 3-8-83
 Operator: Sabre Exploration, Inc.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 7 4 1983
 CONSERVATION DIVISION
 Wichita, Kansas

Depth	Formation	Remarks
From To		
-0- 400	Surface clay	Spudded 2-23-83 @8:45 P.M. Ran 9 joints
400 1904	Shale	8' 5/8", 24# new casing, 378' set @377'.
1904 2765	Shale & Lime	Cemented with 250 sxs 60/40 poz, 3% CC, 2% gel.
2765 3260	Lime & Shale	Cement did cir. Job by Sun. Plug down
3260 3678	Lime & Shale	@2:45 A.M., 2-24-83.
3678 4060	Lime & Shale	
4060 4200	Lime & Shale	R.T.D. 4590'. Plugged well with 50 sxs @
4200 4380	Lime & Shale	2100', 50 sxs @1,050', 40 sxs @450',
4380 4573	Lime & Shale	10 sxs @40' with solid wood plug, 15 sxs
4573 4590	Lime & Shale, R.T.D.	cir. in rat hole with 50-50 poz, 4% gel,
		3% CC. Plug down @1:35 P.M. 3-8-83.
		Job by Sun. Bob Tarbutton, state plugger
		on location.


STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

L. R. Belding
 L. R. BELDING VICE-PRESIDENT

My Commission Expires
 April 23, 1983



Darlene Butts
 Darlene Butts
 Notary Public