

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20399-00-00 ✓

SWSENE Sec. 15, T 16 S, R 27 W/D

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Broughton Well # C-1

Operator: Donald C. Slawson Oil
Name & Producer

County Lane

Address 200 Douglas Bldg. Broadway & Douglas
Wichita, Kansas
67202

Well Total Depth 4585 feet 149.01

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 329

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347 Chase, Kansas 67524

Company to plug at: Hour: 10:00AM Day: 10 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Gene Smith

(company name) Kelso Casing Pulling (phone) _____

were: 1st plug set wood plug @ 4080' dumped 4 bbls cement on top of wood plug through bailer. 2nd sandbed hole back to 4025' & dumped 4 bbls cement on top of it through bailer. 3rd plug squeezed through head w/ 3 bbls hulls & 15 bbls gel & 50 bbls cement & 10 bbls gel & released rubber plug & pumped 125 bbls more of cement.

Signed Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00AM Day: 10 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT This well was plugged as proposed. They plugged it with same procedure as that was proposed. Allied cementing pumped the cement which was 60/40 ppg w/ 2% gel & 3% cc.

Remarks: _____

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 1-16-84
INV. NO. 9115-W

Signed Paul A. Luthi
(TECHNICIAN)