

1060714

API NUMBER 15-101-20,413-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SESWNE SEC. 15, T. 16 S, R. 27 W/D

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Broughton Well # J-1

Operator: Donald C. Slawson
Name &

County Lane 146.25

Address 200 Douglas Bldg.

Well Total Depth 4500 feet

Wichita, Kansas

Conductor Pipe: Size _____ feet _____

67202

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Co. License Number _____

Address Wes City, Kansas

Company to plug at: Hour: 10:00 AM Day: 6 Month: November Year: 1985

Plugging proposal received from Pat Walters

(company name) Slawson (phone) 913-798-2850

well: RTD 1930' - 4 1/2" set @ 1980' Perfs 1738' to 1528'

1st plug pump 2 sbp hulls & 150 sbp cement down 4 1/2"

2nd tie on to 8 5/8" annular & pump as many sbp it will

take, order 50 sbp, 4 1/2" was cemented from TD to surface,

Plugging Proposal Received by Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:05 AM Day: 6 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug pumped 2 sbp hulls & 150 sbp

of cement down 4 1/2" production pipe. Max pressure was

3000 # shut in @ 2700 #. 2nd tie on to 8 5/8" & pumped

5 sbp cement & it locked up @ 4500 # shut in @ 2000 #.

Halliburton Co. pumped 60/40 pack w/ 67 gel.

Remarks: _____
(if additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
Observe this STATE CORPORATION COMMISSION

DATE NOV 22 1985

NOV 8 1985 Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 11155