

1 030808

MAY 3 0 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,387-00-00  
N/2 S/2 NE, SEC. 15, T 16 S, R 27 W/E  
3630 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3258

Lease Name Broughton Well # 1

Operator: Lansing Energy Corporation

County Lane 146.25

Name & Address 204 South Terrace

Well Total Depth 4500 feet

Wichita, KS 67218

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lobo Drilling Company License Number 5864

Address Box 877, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 30 Month: 5 Year: 19 87

Plugging proposal received from Ervin Neighbors

(company name) Lobo Drilling Comapny (phone B16-792-7476)

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2547'  
Anhydrite 1968'

1st plug at 1950' with 50 sx cement, 2nd plug at 1260' with 80 sx cement,

3rd plug at 330' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:15 p.m. Day: 30 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1950' with 50 sx cement,

2nd plug at 1260' with 80 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 2 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied. CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(XXX) did not observe this plugging.

DATE 6-3-87

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 17131

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

# NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date May 18 1987  
month day year

API Number 15- 101-26387

OPERATOR: License # 3238  
Name LANSING ENERGY CORPORATION  
Address 204 South Terrace  
City/State/Zip Wichita, Kansas 67218  
Contact Person Richard L. Cornett  
Phone 316/584-2862

N/2 S/2 NE, Sec. 15, Twp. 16, S, Rg. 27 East  
3630 Ft. from South Line of Section  
1320 Ft. from East Line of Section

CONTRACTOR: License # 5864  
Name LOBO DRILLING COMPANY  
City/State Great Bend, Kansas 67530

(Note: Locate well on Section Plat on reverse side)  
Nearest lease or unit boundary line 330 feet  
County Lane

Well Drilled For:  Oil  Storage  Infield  Mud Rotary  
 Gas  Inf  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Lease Name Broughton Well # 1  
Ground surface elevation 300 feet MSL  
Domestic well within 330 feet  yes  no

If OWWO, old well info as follows:  
Operator  
Well Name  
Comp Date  
Old Total Depth

Municipal well within one mile  yes  no  
Depth to bottom of fresh water 80  
Depth to bottom of usable water 1250

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specification.  
Date May 6, 1987 Signature of Operator or Agent Richard L. Cornett Title Operator

For KCC Use:  
Conductor Pipe Required 11-14-87 feet; Minimum Surface Pipe Required 225 feet per Alt. 40  
This Authorization Expires 11-14-87 Approved By 5-14-87

*More 5-21-87 set 300' of 8 5/8" No*

N/2 S/2 NE, Sec. 15, Twp. 16, S, Rg. 27 East

## PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep	Base Anhydrite	or formation with	50	feet of	60/40 Pozmix 68 gr
2nd plug @ ft. deep	Base Dakota-Cheyenne	or formation with	80	feet of	60/40 Pozmix 68 gr
3rd plug @ ft. deep	330	or formation with	50	feet of	60/40 Pozmix 68 gr
4th plug @ ft. deep	40	or formation with	10	feet of	60/40 Pozmix 68 gr
5th plug @ ft. deep	Rathole	or formation with	12	feet of	60/40 Pozmix 68 gr
(2) Rathole to surface minus 5 feet				(b) Mousehole to surface minus 5 feet	

PUSHER Erwin Neighbors

TD 4500 FORMATION

SURFACE PIPE 8 5/8 @ 298

ANHYDRITE 1968 ELEVATION 2547

STARTING TIME & DATE 2 PM 5-20-87

COMPLETION TIME & DATE 4:15 PM

1st PLUG @ 1950 FT. W/ 50 SX SX

2nd PLUG @ 1260 FT. W/ 80 SX

3rd PLUG @ 330 FT. W/ 40 SX

4th PLUG @ 40-0 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ 15 SX

WATER WELL PLUGGED W/ Hand SX

CEMENT COMPANY 6/4 6% - CC.

TECHNICIAN SA *Allied 2801*

STATE DEPARTMENT OF REVENUE  
JUN 2 1987  
COMMUNICATION DIVISION  
Wichita, Kansas