

To: 1 090218 10-2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,634-00-0017R
30' W & 30' N OF
SE SW NE, SEC. 4, T. 19 S, R. 28 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Suite 1000
Wichita, KS 67202

3000 feet from S section line
1680 feet from E section line
Lease Name Mauler Well # 1
County Lane 151.13
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling Company License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 11 p.m. Day: 1 Month: 10 Year: 19 92

Plugging proposal received from Rocky Milford

(company name) Ritchie Exploration, Inc. (phone) 316-267-4375

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2112-44'
1st plug at 2160' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,
3rd plug at 675' with 50 sx cement, 4th plug at 240' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 a.m. Day: 2 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,
2nd plug at 1320' with 80 sx cement,
3rd plug at 675' with 50 sx cement,
4th plug at 240' with 50 sx cemen,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10-06-1992
OCT 6 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I ~~did not~~ observe this plugging.

Signed [Signature]
(TECHNICIAN)

DATE 10-29-92
INV. NO. 36634

DISTRICT #

NOTICE OF INTENTION TO DRILL 101-21,634-00-00 ALL BLANKS MUST BE FILLED

SEA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 9 19 92 month day year

30' W & 30' N of East SW NE Sec 4 Twp 19 S Rg 29W West

OPERATOR: License # 4767 Ritchie Exploration, Inc. 125 N. Market, Suite 1000 Wichita, KS 67204 Rocky Milford (316) 267-4375

3000 feet from South / North line of Section 1680 feet from East / West line of Section IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # 5420 White & Ellis Drilling Co.

(NOTE: Locate well on the Section Plat on Reverse Side) County: Lane Lease Name: Mauler Well #: 1 Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment: Oil Enh Rec Infield Mud Rotary Gas Storage Pool Ext Air Rotary CWVO Disposal Wildcat Cable Seismic # of Holes Other

Is this a Prorated/Spaced Field? yes X no Target Formation(s): L/KC Nearest lease or unit boundary: 330 Ground Surface Elevation: 2751 feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 100' Depth to bottom of usable water: 1300' Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 200' Length of Conductor pipe required: none Projected Total Depth: 4650' Formation at Total Depth: Mississippian Water Source for Drilling Operations: well farm pond X other DVR Permit #: Will Cores Be Taken? yes X no If yes, proposed zone:

If CWVO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

AFFIDAVIT

200' Alt. II Req.

Exp. 3/15/93 The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Rocky Milford (Ritchie) SPUD DATE 9-19-92 INIT. SP LENGTH SURFACE PLANNED 200' of 8 3/4" RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/4" 207 CONDUCTOR ANHYDRITE T- 2112 B- 2144 ELEVATION TD 4650 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2160 Ft. W/ 50 SX 1/2 Base Anyh. @ 1320 Ft. W/ 80 SX 1/2, 1/2 Plug @ 675 Ft. W/ 50 SX Bottom Surface @ 240 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W/S SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SM DATE 9-22-92 TYPE OF CEMENT 6 1/4 6 9/16 1/4 Flosser STARTING TIME 11:00 (AM) DATE 10-7 RECEIVED 1993 COMPLETION TIME 1:15 (AM) DATE 10-7 CEMENT COMPANY