

1060470

Landowner - Michael G & Glenda K. Keenan

Lease Owner - Slawson

API NUMBER 15- 101-21.111-00-09

To:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 1, T 19 S, R 29W W/E

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Intent filed in wrong Range. M. Dodge in Range 28W

Operator License # 9641

Lease Name M. Dodge Well # 1

Operator: Stauffer Oil & Gas

County Lane

Name &

Address

P. O. Box 6

Well Total Depth 2898 feet

Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 4:00 pm Day: 16 Month: January Year: 19 85

Plugging proposal received from LeRoy Borren & Bob Higginbottom

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2150' with 50 sx cement

2nd plug at 1260' with 40 sx cement

3rd plug at 300' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:45 pm Day: 16 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement, 2nd plug at 1260' with

40 sx cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

JAN 23 1985

01-23-1985

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed

Paul A. Luther

(TECHNICIAN)

DATE

1-28-85

INV. NO.

6666

FORM CP-2/3
Rev. 01-84