

1040963

5-3

API NUMBER 15-101-21,702-00-00

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

NE NW SW, SEC. 1, T 19 S, R 28 W/E  
2310 feet from S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Truax A Well # 1

Operator: Ritchie Exploration, Inc.

County Lane 151.13

Name & Address 125 N. Market, Ste. 1000

Well Total Depth 4650 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address P.O. Box 48848, Wichita, KS 67202-8848

Company to plug at: Hour: 8:45 a.m. Day: 3 Month: 5 Year: 1995

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 2104-32'

1st plug at 2132' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11 a.m. Day: 3 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2132' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floeal by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 05 1995  
05-05-1995  
CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED

observe this plugging.

DATE 5-17-95

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 43842

EFFECTIVE DATE: 4-19-95  
DISTRICT # 1  
SGA? Yes, No

State of Kansas  
NOTICE OF INTENTION TO DRILL 15-101-21,702-00200

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 4 18 95  
month day year

Spot NE NW SW Sec 1 Twp 19 S Rg 28W East West

OPERATOR: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: 125 N. Market, Suite 1000  
City/State/Zip: Wichita, KS 67202  
Contact Person: Rocky Milford  
Phone: (316) 267-4375

2310 feet from South / North line of Section  
990 feet from East / West line of Section  
IS SECTION X REGULAR IRREGULAR?  
(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Lane  
Lease Name: Truax "A" Well #: 1  
Field Name:

CONTRACTOR: License #  
Name: Advise on ACO-1 Well

Is this a Prorated/Spaced Field? yes X no  
Target Formation(s): L/KC, Marm, Miss  
Nearest lease or unit boundary: 330  
Ground Surface Elevation: est 2732 feet MSL  
Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 90' 180'  
Depth to bottom of usable water: 110' 1300'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required:  
Projected Total Depth: 4650  
Formation at Total Depth: Miss  
Water Source for Drilling Operations:  
... well ... farm pond X other

Well Drilled For: Well Class: Type Equipment:  
X Oil Enh Rec Infield X Mud Rotary  
Gas Storage Pool Ext Air Rotary  
OWWO Disposal X Wildcat Cable  
Seismic: # of Holes Other  
If OWWO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location:  
Exp. 10/14/95

DWR Permit #:  
Will Cores Be Taken? yes X no  
If yes, proposed zone:  
200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

AFFIDAVIT RECEIVED

STATE CORPORATION COMMISSION

STATE OF KANSAS  
COURT REPORTER

MAY 05 1995  
05-05-1995

CONSERVATION  
WICHITA, KANSAS

Pusher: Solberg

SPUD DATE: 4-26-95 INIT. Sm

LENGTH SURFACE PLANNED: 200'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/2" @ 207 CONDUCTOR  
ANHYDRITE T-2104 B-2132 ELEVATION  
(2355)

TD 4650 FORMATION  
RAN PIPE @ DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ Ft. W/ SX  
Anhydrite Base @ 2132 Ft. W/ 50 SX  
1/2 Base Anyh. @ 1350 Ft. W/ 80 SX  
1/2, 1/2 Plug @ 650 Ft. W/ 50 SX  
Bottom Surface @ 230 Ft. W/ 40 SX  
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond  
Hauling  
TECHNICIAN SP DATE 4-28-95

TYPE OF CEMENT 60/90 port 6 gal @ 14 FS

STARTING TIME 8:45 (AM) DATE 5-3-95

COMPLETION TIME 11:00 (AM) DATE 5-3-95

CEMENT COMPANY Milford