

TO: 1080193

S-11

API NUMBER 15-101-21,762-00-00

STATE CORPORATION COMMISSION NE SW NE, SEC. 1, T 19 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 1685 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1671 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME PALMER TRUST WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 150.61

OPERATOR LICENSE # 4767 WELL TOTAL DEPTH 4634' FEET

OPERATOR: RITCHIE EXPLORATION, INC. PRODUCTION CSG: SIZE FEET  
NAME AND P.O. BOX 783188 SURFACE CASING: SIZE 8 5/8" FEET 207'

ADDRESS WICHITA, KS 67278-3188

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ABERCROMBIE RTD INC. LICENSE NUMBER 30684

ADDRESS 150 N.MAIN, STE. 80 WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 11 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM GARY WINTERS

(COMPANY NAME) ABERCROMBIE RTD INC. (PHONE) 316-262-1841  
WERE: TO FILL HOLE WITH HEAVY MUD AND SPOT CEMENT THROUGH PIPE

1ST PLUG AT 2150' WITH 50 SX CEMENT, 2ND PLUG AT 1220' WITH 80 SX CEMENT,  
3RD PLUG AT 610' WITH 40SX CEMENT, 4 TH PLUG @230' WITH 50 SX CEMENT, 5TH PLUG AT 0-40' WITH  
10 SX CEMENT

CIRCULATE RATHOLE WITH 15 SX OF CEMENT

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 11 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT 1ST PLUG AT 2150' WITH 50 SX CEMENT,  
2ND PLUG AT 1220' WITH 80 SX CEMENT,  
3RD PLUG AT 610' WITH 40 SX CEMENT,  
4TH PLUG AT 230' WITH 50 SX CEMENT,  
5TH PLUG AT 40' CIRCULATE CEMENT TO SURFACE WITH 10 SX CEMENT

CIRCULATED RATHOLE FULL WITH 15 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL1/4 FLOW SEAL, CEMENT PUMPED BY ALLIED CEMENTING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P. Strube (TECHNICIAN) FORM CP-2/3 RECEIVED STATE COMMISSION

INVOICED

DATE MAY 14 1998

DATE

TEL. NO. 50563

MAY 13 1998 05-13-1998

EFFECTIVE DATE: 4-19-98

DISTRICT # 1  
SSA7... Yes  No

10-14-98

State of Kansas  
NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

ALT II  
FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Expected Spud Date April 25 1998  
month day year  
Spot NE SW NE Sec 1 Twp 19 S Rg 28 East

OPERATOR: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: P.O. Box 783188  
City/State/Zip: Wichita, Kansas 67278-3188  
Contact Person: Julie Stout  
Phone: (316) 691-9500

RECEIVED  
INSAS 1685  
11/16/98  
11/16/98  
IS SECTION 8 REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Lane  
Lease Name: Palmer Trust Well #: 1  
Field Name: SELFRIED SE

CONTRACTOR: License #: ADVISE ON ACO-1 30684  
Name: Apurambou R.T.O. Inc

Is this a Prorated/Spaced Field? ... yes  no  
Target Formation(s): L/KC, Mississippian  
Nearest lease or unit boundary: 330+ 365'  
Ground Surface Elevation: ... est. 2736 ... feet MSL  
Water well within one-quarter mile: ... yes  no  
Public water supply well within one mile: ... yes  no  
Depth to bottom of fresh water: 90 180  
Depth to bottom of usable water: 1190  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required: none  
Projected Total Depth: 4650'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well ... farm pond  other

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec X Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWVO ... Disposal X Wildcat ... Cable  
... Seismic: ... # of Holes ... Other  
... Other  
If OWVO: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes  no  
If yes, true vertical depth:  
Bottom Hole Location:

DWR Permit #:  
Will Cores Be Taken? ... yes  no  
If yes, proposed zone:

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Tony Marban  
SPUD DATE 5-2-98 INIT. SM  
LENGTH SURFACE PLANNED 200ft

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8" @ 307 CONDUCTOR  
ANHYDRITE T- 209 B-2126 ELEVATION

TD 4650 FORMATION MISS.  
RAN PIPE @ SX DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @ Ft. W/ SX  
Hug./Council @ 230 Ft. W/ SX  
Anhydrite Base @ 2450 Ft. W/ 50 SX  
1/2 Base Anhyd. @ 1220 Ft. W/ 80 SX  
1/2, 1/2 Plug @ 610 Ft. W/ 40 SX  
Bottom Surface @ 230 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond  
TECHNICIAN GW DATE 5-7-98 Hauling  
TYPE OF CEMENT 60/40 Pozzomix 1 1/2 Ft  
STARTING TIME 9:35 (AM/PM) DATE 5-11-98  
COMPLETION TIME 12:00 (AM/PM) DATE 5-11-98  
CEMENT COMPANY Allied