

1051412

3-12

API NUMBER 19- 101-21,570-00-00  
80' N of NW SE SE, SEC. 25, T. 19 S, R. 28 W/E

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1070 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Nelson Schwartz Well # 1

Operator: Ritchie Exploration, Inc.

County Lane 151-12

Name & Address 125 N. Market, Suite 1000  
Wichita, KS 67202

Well Total Depth 4650 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling Company License Number 5420

Address 401 E. Douglas, #500, Wichita, KS 67202

Company to plug at: Hour: 2:30 p.m. Day: 12 Month: 3 Year: 19 91

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling Company (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2035-65'

1st plug at 2065' with 50 sx cement, 2nd plug at 1250' with 80 sx cement,

3rd plug at 625' with 50 sx cement, 4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5 p.m. Day: 12 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2065' with 50 sx cement,

2nd plug at 1250' with 80 sx cement,

3rd plug at 625' with 50 sx cement,

4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

Did you observe this plugging.

INVOICED

DATE 4-3-91

INV. NO. 31306

Signed Richard W. Lacy (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
03-15-1991  
MAR 15 1991  
CONSERVATION DIVISION  
Wichita, Kansas

EFFECTIVE DATE: 2-9-91

State of Kansas

101-21,570 0000

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 2/10/91  
month day year

30' N 7'  
NW SE SE Sec 25 Twp 19S, Rg 28 X East West

OPERATOR: License # 4767  
Name: Ritchie Exploration, Inc.  
Address: 125 N. Market, Suite 1000  
City/State/Zip: Wichita, KS 67202  
Contact Person: Rocky Milford  
Phone: 316/267-4375

1070' feet from South line of Section  
990' feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5420  
Name: White & Ellis Drilling Co.

County: Lane  
Lease Name: Nelson Schwartz Well #: 1  
Field Name: wildcat  
Is this a Prorated Field? yes X no  
Target Formation(s): Lansing/KC  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: est. 2721' feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 75'  
Depth to bottom of usable water: 1175'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required: none  
Projected Total Depth: 4650'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
well farm pond X other

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWWO ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes

If OWWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal well bore? Yes X no  
If yes, total depth location: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
03-15-1991  
MAR 15 1991

Exp. 8/4/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Judy  
SPUD DATE 3-4-91 INIT. R.C.  
LENGTH SURFACE PLANNED 200  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. ... bbls. when done ... bbls.  
RATHOLED AHEAD? N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 8 7/8 @ 208 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T-2035 B-2065 ELEVATION \_\_\_\_\_  
TD 4650 FORMATION MISS  
RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX \_\_\_\_\_ Y \_\_\_\_\_ N \_\_\_\_\_  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
1 Anhydrite Base @ 2065 Ft. W/ 50 SX  
2 1/2 Base Anhy. @ 1250 Ft. W/ 80 SX  
3 1/2, 1/2 Plug @ 625 Ft. W/ 50 SX  
4 Bottom Surface @ 230 Ft. W/ 40 SX  
5 40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/40 SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
Hauling \_\_\_\_\_  
TECHNICIAN SP DATE 3-8-91  
TYPE OF CEMENT 60/40 puz 6 gal + 1/4 Flow Seal  
STARTING TIME 2:30 (AM/PM) DATE 3-12-91  
COMPLETION TIME 5:00 (AM/PM) DATE 3-12-91  
CEMENT COMPANY Lacey Allied  
Lacey Saw part