

1 050865

DEC 30 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,279 -00-00

NE SE NW, SEC. 23, T 19 S, R 28 W/E  
3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5104

Lease Name Starr Well # 1

Operator: Blue Goose Drilling Company, Inc.  
Name & Address P.O. Box 1413, Great Bend, KS 67530

County Lane 152.91  
Well Total Depth 4705 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 30 Month: 12 Year: 1986

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 4400' PBDT 4348' Perfs at 4311-12' Elevation 2757'GL

1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
release 8 5/8" wiper plug and pump 165 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 30 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 4 sx cement on top of sand  
through bailer,

2nd plug pumped down 8 5/8" with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
released 8 5/8" wiper plug and pumped 165 sx cement.

STATE CORPORATION COMMISSION

01-05-1987  
JAN 5 1987

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Recovered 2250' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

(111) (111) observe this plugging.

DATE 1-6-87

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 15798