

1 030441

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2 NW SE, SEC. 23, T 19 S, R 28 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,162-01-00  
1980 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9896  
Operator: Bonray Energy Corporation  
Name & Address: P. O. Box 20746  
Oklahoma City, OK 73156

Lease Name Hineman Well # 23-1  
County            Lane 150.15  
Well Total Depth 4620 (Ft. Scott) feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 980

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor H-30 Drilling, Inc. License Number 5107  
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 20 Month: June Year: 19 85

Plugging proposal received from Rick Davis

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2759'  
Anhydrite 2111'

1st plug at 2100' with 50 sx cement

2nd plug at 1020' with 50 sx cement

3rd plug at 510' with 25 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)  
X

Plugging Operations attended by Agent?: All            Part            None           

Operations Completed: Hour: 6:00 am Day: 20 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1020' with 50  
sx cement, 3rd plug at 510' with 25 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1985  
06-24-1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)  
observe this plugging.

DATE 6-24-85

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 8662 6-20

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

Hineman #1 2155' - 220' 23-19-28  
CARD MUST BE SIGNED

Starting Date: 5 15 85  
month day year

API Number 15-101-21,162-0000  
C W 1/2 NW 1/4 SE 1/4 Sec 23 Twp 19 S, Rge 28

OPERATOR: License # 9896  
Name Bonray Energy Corporation  
Address P. O. Box 20746  
City/State/Zip Oklahoma City, OK 73156  
Contact Person Lee Troiani  
Phone 405-848-6891

1980..... Ft North from Southeast Corner of Section  
2310..... Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107  
Name H-30 Wellbore Inc  
City/State 251 N W 100th, Suite 10, Wichita, KS 67202

Nearest lease or unit boundary line 330 feet  
County Lane  
Lease Name Hineman Well# 23-1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 200 feet  
Lowest usable water formation 200 Dakota  
Depth to Bottom of usable water 200 950 feet

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4700 feet  
Projected Formation at TD Ft. Scott  
Expected Producing Formations Lansing/KC

Surface pipe by Alternate: 1  2   
Surface pipe to be set 950 feet  
Conductor pipe if any required N/A feet  
Ground surface elevation 2759 feet MSL  
This Authorization Expires 10-16-85  
Approved By 4-16-85 R

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 4 4/15/85  
Signature of Operator or Agent Lee Troiani  
970-85/8

Title Mgr. Prod. & Engineering  
mhc/wohe 4-16-85  
Form C-1 4/84

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1985  
06-21-1985  
CONSERVATION DIVISION  
Wichita, Kansas