

1 030326

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,070-00-00

NW SW NW , SEC. 22 , T 19 S, R 28 (W) X

3630 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Missionary Well # 1-22

Operator: Texas Energies, Inc.

County Lane 153.79

Name & Address P. O. Box 947

Well Total Depth 4732 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co. License Number 5057

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 8 Month: November Year: 19 84

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2140' with 50 sx cement

2nd plug at 810' with 50 sx cement

3rd plug at 390' with 50 sx cement

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement

Plugging Proposal Received by Steve Aumont (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 pm Day: 8 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2140' with 50 sx cement, 2nd plug at 810' with 50 sx

cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

NOV 15 1984

11-15-1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did not) observe this plugging.

DATE 11-27-84

Signed Steve Aumont (TECHNICIAN)

INV. NO. 4901 11-8