

1 070240

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Operator: Palomino Petroleum
Name & Address: Route 5, Box 51-C
Newton, KS 67114

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Mallard JV, Inc. License Number 4958

Address Mc Pherson, KS 67460

Company to plug at: Hour: 6:30 p.m. Day: 4 Month: 11 Year: 19 86

Plugging proposal received from Arnie Hess

(company name) Mallard JV, Inc. (phone) 913-731-2869

were: to fill hole with heavy mud and spot cement through drill pipe. Anhydrite 2122-53'
1st plug at 2140' with 50 sx cement, 2nd plug at 1400' with 50 sx cement,
3rd plug at 350' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with
10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8:30 p.m. Day: 4 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,
2nd plug at 1400' with 70 sx cement,
3rd plug at 375' with 50 sx cement,
4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (do not observe this plugging.)

DATE 11-7-86

INV. NO. 15306

API NUMBER 15- 101-21,340-00-00

NW SE SW, SEC. 22, T 19 S, R 28 (W/E)

990 feet from S section line

3630 feet from E section line

Lease Name Missionary Well # 1

County Lane 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 346

11-06-1986
NOV 6 1986

Signed Dan Goodrow (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

2

Starting Date 10 month 6 day 86 year

OPERATOR: License # 5161
Name Palomino Petroleum
Address Route 5, Box 51-C
City/State/Zip Newton, KS 67114
Contact Person Bob Watchous
Phone (316) 283-0232

CONTRACTOR: License # 4958
Name Mallard JV, Inc.
City/State McPherson, KS 67460

Well Drilled For: X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 9-29-86 Signature of Operator or Agent *Bob Watchous* Title Owner *PC4/KCC*

For KCC Use:
Conductor Pipe Required feet: Minimum Surface Pipe Required 200 feet per Alt. 12
This Authorization Expires 3-30-87 Approved By 9-30-86 *PC4/KCC*

Move in 10-24-86 set 320+

API Number 15-101-21,340-00700
NW SE SW Sec. 22 Twp. 19 S. Rg. 28 X East
990 Ft. from South Line of Section
3630 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990 feet
County Lane
Lease Name Missionary Well # 1
Ground surface elevation 2775 est. feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 80
Depth to bottom of usable water 1050 1300
Surface pipe planned to be set 320+
Projected Total Depth 4730 feet
Formation Miss.

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2140	feet depth with	50	sxs of cement
2nd plug @ 1400	feet depth with	50	sxs of cement
3rd plug @ 350	feet depth with	50	sxs of cement
4th plug @ 40 to 0	feet depth with	10	sxs of cement
5th plug @	feet depth with		sxs of
(2) Rathole with 15	sxs		(b) Mousehole with 10 sxs

PUSHER Annie Hess
TD 4750' FORMATION Miss.
SURFACE PIPE 8 5/8" @ 346'
ANEHYDRITE 2/22-83 ELEVATION 2775' est.
STARTING TIME & DATE 6:30 PM 11-4-86
COMPLETION TIME & DATE 8:30 PM 11-4-86
1st PLUG @ 2150' FT. W/ 50 SX
2nd PLUG @ 1400' FT. W/ 70 SX
3rd PLUG @ 375' FT. W/ 50 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
60/40 ps. 69.9c
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN Dan Gandy, Saw All

6 1980
11-06-1984