

1 050870

JAN 9 1987

API NUMBER 15-101-20,929-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE SW, SEC. 21, T 19 S, R 28

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Larry Well # 1

Operator: Palomino Petroleum

County Lane 153.56

Name & Address Route 5, Box 51-C

Well Total Depth 4725 feet

Newton, KS 67114

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 12 p.m. Day: 7 Month: 1 Year: 19 87

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4720' PBD 4670' Perfs at 4390-92'

1st plug pump 1 sx hulls and 20 sx cement,

2nd plug at 1325' with 70 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 10 a.m. Day: 9 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT pumped 2 sx hulls and 20 sx cement and stopped plug at 4392' - shot pipe at 1325' - could not pull pipe or pump cement into it - shot pipe at 1000' - could not pull pipe or pump cement into it - shot pipe at 800' - could pull pipe but couldn't pump into zone.

1st plug pulled pipe to 625' - pumped 60 sx of common cement.

2nd plug pulled pipe to 350' - pumped 50 sx of common cement.

3rd plug top off hole at 40-0' with 10 sx of common cement.

Remarks: Used common cement by Sargent's. Recovered 826' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
01-12-1987
JAN 13 1987
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

DATE 1-13-87

Signed Richard W. Lacey (TECHNICIAN)

REV. NO. 15903