



15-169-30016-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

December 22, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

12-29-69
DEC 29 1969

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Melland Drilling Company

Complete Address: Box 783, Mc Pherson, Kansas 67460

Lease Name: Ivan Henne Well No. 1

Location: N/2 NW SE Sec. 8 Twp. 16 Rge. 1 (E) (W) X

County: Saline Total Depth 2688' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 2650' and cement with 5 sacks cement.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and
cement hole with 30 sacks cement. Fill hole with mud to 40'. Set rock
bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

William B. Loman
Conservation Division Agent