



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
10-26-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drlg. Co., Inc. has this

date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Patrick Petroleum Corporation,

Complete Address: Suite 300, 220 W. Douglas, Wichita, Kansas

Lease Name: Speck Well No. 1

Location: NE-SE-NW Sec. 1 Twp. 17 Rge. (E)(W) 28

County: Lane Total Depth 4367' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

333'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 950' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent