

State of Kansas



15-101-20103-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

RECEIVED STATE CORPORATION COMMISSION

JUN 17 1974 6-17-74 CONSERVATION DIVISION Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Drlg. has this

date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Inc.

Complete Address: Rt #2 Victoria, Kansas

Lease Name: Schneider Well No. 1

Location: C. W/2 E/2 NW Sec. 12 Twp. 17 Rge. (E)(W) 28

County: Lane Total Depth 4650' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1200' and displace 70 sk cmt thru drill pipe, Heavy mud to 185' set cementing plug and displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Red F. Massey Conservation Division Agent