

State of Kansas



15-101-20076-0000

State Corporation Commission

CONSERVATION DIVISION

Oil, Gas and Water)
P. O. Box 17027, 1930 S. Meridian
WICHITA, KANSAS 67227

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1973
12-12-73
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filled By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Oden of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc.

Complete Address: Box 18407 Wichita, Ks.

Lease Name: Davis "B" Well No. 3

Location: A/C SW SE Sec. 13 Twp. 17 Rge. (E)(W) 28

County: Lane Total Depth 4640' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Oden was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1000' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Messing
Conservation Division Agent