



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

MAR 6 1974  
3-6-74  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton,

Complete Address: 800 Sutton Place, Wichita, Kansas.

Lease Name: Waterson Well No. 1

Location: CSE-NE Sec. 13 Twp. 17 Rge. (E)(W) 28

County: Lane Total Depth 4640' Oil Well     

Gas Well      Input Well      SWD Well      D & A      Lost Hole X

Mr. Dreiling was instructed to plug the well as follows:

393'--8 5/8" Surface casing, cement circulated with 250 Sx.  
4619'--5 1/2" Production casing cemented on bottom with top of cement @  
3800'. 5 1/2" casing collapsed @ 3180', broke circulation around 5 1/2" but  
was unable to pull. 5 1/2" casing shot off @ 1350'.

Pull 5 1/2" casing to 975' and displace 110 Cu. Ft. cement thru 5 1/2". Pull  
5 1/2" to 400' and displace 30 Cu. Ft. cement thru 5 1/2". Pull 5 1/2", set  
bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*M. L. Nichols*  
Conservation Division Agent