

State of Kansas



15-101-20107-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 11 1974
11-11-74
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Elmo Morgenstern of Clarke Corporation has this date requested permission to plug the following described well:

Mr. Morgenstern guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Royalty Well No. A-1

Location: CSE-NE Sec. 9 Twp. 15 Rge. (E)(W) 28

County: Lane Total Depth 4660' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Morgenstern was instructed to plug the well as follows:

249'--8 5/8 " Surface casing, cement circulated with 200 Sx.
4325'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4285'. Top of perforations @ 4285'.

Sand well back to 4200' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent