

1 050882

83

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,362 -00-00
NW NE SE, SEC. 21, T 19 S, R 28 (W/R)
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Mowery Trust Well # 3

Operator: Palomino Petroleum

County Lane 154.21

Name & Address Route 5, Box 51-C

Well Total Depth 4745 feet

Newton, KS 67114

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 219

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard J.V. Inc. License Number 4958

Address 2080 East Kansas, Box 1009, McPherson, KS 67460

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 2 Year: 1987

Plugging proposal received from Arnie Hess

(company name) Mallard J.V. Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2137'

1st plug at 2140' with 50 sx cement, 2nd plug at 1400' with 50 sx cement,

3rd plug at 240' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1 p.m. Day: 16 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 2140' with 50 sx cement, 2nd plug at 1400' with 50

sx cement, 3rd plug at 240' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this report.)

INVOICED observe this plugging.

02-19-1987
FEB 19 1987

DATE 2-20-87

Signed Richard M. Long (TECHNICIAN) STATE CORPORATION COMMISSION
Wichita, Kansas

INV. NO. 16185

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date Feb 9 1987 month day year

API Number 15- 101-21,362-00-00

OPERATOR: License # 5161 Name Palomino Petroleum Address Route 5 Box 51-C City/State/Zip Newton, KS 67114 Contact Person Bob Watchous Phone (316) 283-0232

NW NE SE Sec. 21 Twp. 19 S, Rg. 28 X West 2310 990 Ft. from South Line of Section Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4958 Name Mallard J.V., Inc. City/State McPherson, KS

Nearest lease or unit boundary line 330 feet County Lane

Well Drilled For: X Oil SWD Well Class: X Infield Type Equipment: X Mud Rotary

Lease Name Mowery Trust Well # 3

Ground surface elevation 2780 Est. feet MSL

Domestic well within 330 feet: yes X no

Municipal well within one mile: yes X no

Depth to bottom of fresh water 80

Depth to bottom of usable water 1300

Surface pipe by Alternate: 1-2 X

Surface pipe planned to be set 200'+

Conductor pipe required

Projected Total Depth 4750 feet

Formation Miss.

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 1-30-87 Signature of Operator or Agent Bob Watchous Title Owner

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 8-2-87 Approved By 2-2-87

Moores 2-6-87

8 1/2 - 200

Don 2/19/87 8 1/2

for KCC No

9N 2 1/2 E East

Sec. Twp. S, Rg. West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, feet depth with, size of casing, and cement type. Includes entries for 1st through 5th plugs and a mousehole.

Vertical list of well parameters: PUSHER Arnie Hess, TD 4745, SURFACE PIPE 8 1/2 @ 219, ANHYDRITE 2137' ELEVATION 10:30 am, STARTING TIME & DATE 2-16-87, COMPLETION TIME & DATE 2/19/87 1:00 pm, 1st PLUG @ 2140 FT. W/ 50 SX, 2nd PLUG @ 1400 FT. W/ 50 SX, 3rd PLUG @ 240 FT. W/ 50 SX, 4th PLUG @ 40 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ 10 SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Allied, TECHNICIAN Lacey saw part

STATE CORPORATION COMMISSION

02-19-1987 FEB 19 1987

CONSERVATION DIVISION Wichita, Kansas