

To: 1 041252  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

5-29 API NUMBER 15- 101-21,739-00-00  
SW NW NW, SEC. 21, T 19 S, R 28 W/X  
990 feet from N section line  
330 feet from W section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6039  
Operator: L.D. Drilling, Inc.  
Name & Address  
RR 1, Box 183 B  
Great Bend, KS 67530

Lease Name Thomas Well # 1  
County Lane 151.94  
Well Total Depth 4675 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039  
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: \_\_\_\_\_ Day: 29 Month: 5 Year: 19 97

Plugging proposal received from Greg Davidson  
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2136-64'  
1st plug at 2164' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,  
3rd plug at 650' with 50 sx cement, 4th plug at 300' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 a.m. Day: 29 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2164' with 50 sx cement,  
2nd plug at 1350' with 80 sx cement,  
3rd plug at 650' with 50 sx cement,  
4th plug at 300' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

~~XXXX~~ / did not observe this plugging.

INVOICED  
DATE JUN 06 1997

INV. NO. 48244  
5-29

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
1997 JUN - 2 A 3:38

06-02-1997

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 3-31-97

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 101-21,739-00-00 ALL BLANKS MUST BE FILLED

FORM MUST BE SIGNED

SGA7... Yes... X No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date May 15 1997

Spot SW NW NW Sec 21 Twp 19 S Rg 28 East West

OPERATOR: License # 6039
Name: L. D. DRILLING, INC.
Address: R.R. 1 Box 183 B
City/State/Zip: Great Bend, Kansas 67530
Contact Person: L. D. Davis
Phone: (316) 793-3051

990 feet from South North line of Section
330 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 6039
Name: L. D. DRILLING, INC

(NOTE: Locate well on the Section Plat on Reverse Side)
County: LANE
Lease Name: THOMAS Well #: 1
Field Name: unnamed

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWWO Disposal Wildcat Cable
Seismic; # of Holes Other

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2781 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 124 180
Depth to bottom of usable water: 1300
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 250'
Length of Conductor pipe required: none
Projected Total Depth: 4700'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations: well farm pond other

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Will Cores Be Taken? yes X no
If yes, proposed zone:
200' Alt. II Req.

Exp: 9/26/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher: L. D. Davis
SPUD DATE: 5-22-97 INIT. LDW
LENGTH SURFACE PLANNED: 250 FT
RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/4 @ 271 CONDUCTOR
ANHYDRITE T-2134 B-2464 ELEVATION (4575)
TD 4625 FORMATION
RAN PIPE @ DV TOOL ALT II DONE SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 2164 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1350 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 650 Ft. W/ 50 SX
4 Bottom Surface @ 300 Ft. W/ 50 SX
5 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN SP DATE 5-28-97
TYPE OF CEMENT 60/40pez 6 gal 1/4 Flow Sand
STARTING TIME (AM/PM) DATE
COMPLETION TIME 2:30 (AM/PM) DATE 5-29-97
CEMENT COMPANY Allied

06-02-1999

RECEIVED FOR KANSAS CORPORATION