

1 090374

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,341-00-0φ
50' W. of SW NE SE, SEC. 21, T 7, R 19 S, R 28 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 30742

Operator: Palomino Petroleum, Inc.

Name & Address: 4924 SE 84th St.

Newton, KS 67114-8827

1650 feet from S section line

1040 feet from E section line

Lease Name Mowery Trust Well # 2 (TWIN)

County Lane

Well Total Depth 4738 153.99 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Palomino Petroleum, Inc. License Number 30742

Address 4924 SE 84th St., Newton, KS 67114-8827

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 12 Year: 1993

Plugging proposal received from Steve Robben

(company name) Palomino Petroleum, Inc. (phone) 913-735-9405

Work: 5 1/2" at 4734' w/650 sx cement, PBTD 4375', Perfs at 4337-40', Upper stage cemented w/ 400 sx cement

1st plug hook onto 5 1/2" casing and pump in 2 sx hulls, 50 sx cement, 12 sx gel, and 150 sx cement.

Check backside: .

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 10 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug hooked onto 5 1/2" casing and pumped in 2 sx hulls, 50 sx cement, 12 sx gel, and 150 sx cement. Maximum pressure 1000 psi and shut in 800 psi.

Hooked onto backside, shut in pressure 300#.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 12-30-93

INV. NO. 39603

Signed [Signature] (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

DEC 16 1993

12-16-1993

CONSERVATION DIVISION Wichita, Kansas