

To: 1090505 11-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
260 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,283-00-00

SE SW NE NW, SEC. 19, T 19 S, R 28 W/E

4270 feet from S section line

3500 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30104

Operator: Paul L. Cambron

Name & Address: 118 N. Penn

Ness City, KS 67560-0384

Lease Name H.G. Hinneman Well # 1

County Lane

Well Total Depth 4753 154.47 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied License Number

Address Ness City, KS

Company to plug at: Hour: 10:25 a.m. Day: 29 Month: 11 Year: 1994

Plugging proposal received from Moe

(company name) Paul Cambron (phone) 913-798-2282

were: 5 1/2" at 4737' w/200 sx cement. DV @ 2135' w/350 sx cement. Perfs at 4344-62, 4648-58'
1st plug pump 300 lbs. hulls and 325 sx cement to 4650'.

Check backside.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 29 Month: 11 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls with 325 sx cement down 5 1/2" casing.

Maximum pressure 1000 psi and shut in 100 psi.

Backside full of cement - could not pump into.

RECEIVED STATE CORPORATION COMMISSION 12-01-1994 DEC 01 1994 CONSERVATION DIVISION WICHITA, KANSAS

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery. (If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

Signed [Signature] (TECHNICIAN)

INVOICED

DATE 12-6-94

INV. NO. 41816

11-29 FEB 16 1995