

1100298

TO: STATE CORPORATION COMMISSION 6-18

API NUMBER 15-101-21,767-00-00
NE SE NW SEC. 17, T 19 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME THOMAS "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 152.75

OPERATOR LICENSE # 9408 WELL TOTAL DEPTH 4700 FEET

OPERATOR: TRANS PACIFIC OIL CORPORATION PRODUCTION CSG: SIZE " FEET

NAME AND 100 S MAIN, SUITE 200 SURFACE CASING: SIZE 8 5/8" @ 205' WITH SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SHIELDS DRILLING LICENSE NUMBER 5184

ADDRESS PO BOX 709 RUSSELL, KS 67665-0709

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 18 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM BURT BEERY

(COMPANY NAME) SHIELDS DRILLING (PHONE) 785-483-3141

WERE:

1ST PLUG AT 2200' WITH 50 SX CEMENT. 2ND PLUG AT 1200' WITH 80 SX CEMENT.

3RD PLUG AT 650' WITH 40 SX CEMENT. 4TH PLUG AT 240' WITH 30 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 5:10 PM DAY: 18 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2200' WITH 50 SX CEMENT. 2ND PLUG AT 1200' WITH 80 SX CEMENT.

3RD PLUG AT 650' WITH 40 SX CEMENT. 4TH PLUG AT 240' WITH 30 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

DATE 7-9-99

SIGNED Gary Winters
(TECHNICIAN) FORM CP-2/3

INV. NO. 60023

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas
RECEIVED
JUL 12 1999
07-02-1999
[Signature]