

4-19-90

157 R

To: 1051293
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,495-00-01
SW NE NW, SEC. 17, T 19 S, R 28 W/EK
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656
Operator: Davis Petroleum, Inc.
Name & Address: Route 1, Box 183-B
Great Bend, KS 67530

Lease Name Thomas Well # 1
County Lane
Well Total Depth 4500 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 19 Month: 4 Year: 1990

Plugging proposal received from Gary Burke

(company name) Great Behd Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4495' Perfs at 4327-30'

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 160 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 19 Month: 4 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 4 sx cement on top of sand through bailer,

2nd plug shot 4 1/2" at 1210' and pumped 60 sx cement, displaced to 1100',

Pulled 786' of 4 1/2",

3rd plug pumped down 8 1/2" with 400 lbs. hulls and 100 sx cement.

Maximum pressure 500 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 786' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 5-3-90 APR 23 1990

INV. NO. 28019 CONSERVATION DIVISION Wichita, Kansas

Signed Richard W. Lacey (TECHNICIAN)