

To: 1 070665
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-26
API NUMBER 15-101-20,892-~~100~~-01

SE SE SE, SEC. 17, T 19 S, R 28 W/E

330 feet from S section line

330 feet from E section line

Lease Name Thomas "KS" Well # 1

County Lane 141.05

Well Total Depth 4340 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 343

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Operator: Davis Petroleum, Inc.

Name &

Address RR 1, Box 183-B

Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling License Number 5420

Address 401 East Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 26 Month: 4 Year: 19 89

Plugging proposal received from Bob Kasper

(company name) White & Ellis Drilling (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2775' Anhydrite 2125-56'

1st plug at 2150' with 50 sx cement, 2nd plug at 1400' with 75 sx cement,

3rd plug at 365' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:15 p.m. Day: 26 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1400' with 75 sx cement and 100 lbs. hulls,

3rd plug at 365' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 5-8-89

INV. NO. 24634

Signed Dan Goodrow (TECHNICIAN)

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... April 25, 1989
month day yearSE SE SE Sec 17 Twp 19 S, Rg 28 East
WestOPERATOR: License # 4656
Name: Davis Petroleum, Inc.
Address: RR 1 Box 183-B
City/State/Zip: Great Bend, KS 67530
Contact Person: L.D. Davis
Phone: 918-584-3581330 feet from South line of Section
330 feet from East line of Section
(Note: Locate well on Section Plat Below)CONTRACTOR: License #: 5420
Name: White and Ellis DrillingCounty: Lane
Lease Name: Thomas "KS" Well #: 1
Field Name: Wildcat
Is this a Prorated Field? yes X no
Target Formation(s): LKC
Nearest lease or unit boundary: 330
Ground Surface Elevation: 2775 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 120
Depth to bottom of usable water: 1100
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe ~~XXXXXX~~ set: 343'
Length of Conductor pipe required: None
Projected Total Depth: 4710
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond X ... other
DWR Permit #: City Water
Will Cores Be Taken? yes X no
If yes, proposed zone:Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
X OWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

If OWO: old well information as follows:


Operator: Donald C. Slawson
Well Name: Coberly 'BI' #1
Comp. Date: 12/19/83 Old Total Depth: 4710Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Spud 4-21-89 9:00am

AFFIDAVIT

3431' Ker

PUSHER	TD	FORMATION	SURFACE PIPE @	ANHYDRITE	ELEVATION	STARTING TIME & DATE	COMPLETION TIME & DATE	1st PLUG @	2nd PLUG @	3rd PLUG @	4th PLUG @	RAT HOLE CIRCULATED W/	MOUSE HOLE CIRCULATED W/	WATER WELL PLUGGED W/	CEMENT COMPANY	TECHNICIAN
								FT. W/	FT. W/	FT. W/	FT. W/					

RECEIVED
STATE CORPORATION COMMISSIONMAY 1 1989
05-01-1989
CONSERVATION DIVISION
Wichita, KansasIN CONSERVATION DIVISION
Wichita, Kansas

Spud date: Agent:

REMEMBER TO:

- File Drill Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.