

1 070583

9-6

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,483-00-00
NE NE SW, SEC. 14, T 19 S, R 28 WAE

TECHNICIAN'S PLUGGING REPORT

Operator License # 8541

Lease Name Sleeper Well # 1

Operator: Petex, Inc.

County Lane 153.40

Name & Address
1111 South Glenstone, Suite 1-104
Springfield, MO 65804

Well Total Depth 4720 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 4:15 p.m. Day: 6 Month: 9 Year: 19 88

Plugging proposal received from George Miller

(company name) Blue Goose Drilling (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2754'
Anhydrite 2122-50'

1st plug at 2150' with 50 sx cement, 2nd plug at 1500' with 75'sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:15 p.m. Day: 6 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1500' with 75 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (XXX) did not observe this plugging.

DATE 9-14-88

INV. NO. 22239

Signed Dan Goodrow (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. October 30, 1988
month day year

API Number 15-101-21,483-00:00

OPERATOR: License # 8541
 Name Petex, Inc.
 Address 1111 S. Glenstone, #1-104
 City/State/Zip Springfield, MO 65804
 Contact Person Larry Childress
 Phone (417) 862-2177

NE NE SW 14 Sec. 19 Twp. 28 S, Rg. 28 East
2310 West
2970 Ft. from South Line of Section
 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5104
 Name Blue Goose Drilling
 City/State Great Bend, KS
 Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ Storage ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

Nearest lease or unit boundary line 330 feet
 County Lane
 Lease Name Sleeper Well # 1
 Ground surface elevation 2754 feet MSL.
 Domestic well within 330 feet: ☐ yes ☒ no
 Municipal well within one mile: ☐ yes ☒ no
 Depth to bottom of fresh water 100
 Depth to bottom of usable water 1200 1250
 Surface pipe by Alternate: 1 2 ☒
 Surface pipe planned to be set 200
 Conductor pipe required
 Projected Total Depth 4700 feet
 Formation Miss

If OWWO: old well info as follows:

Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8/15/88 Signature of Operator or Agent L Childress Title President

For KCC Use:

Conductor Pipe Required 200' feet; Minimum Surface Pipe Required 200' feet per Alt. ☒ (2)This Authorization Expires 2-18-89 Approved By LKM 8-18-88EFFECTIVE DATE: 8-23-88Spud 8-29-88200' of 8 5/8"wt. well NONE NE SW. Sec. 14 Twp. 19 S, Rg. 28 East
West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep top of Anhydrite formation with 20 feet of 60-40 pozmix 6% gel
 2nd plug @ ft. deep base of Dakota or formation with 100 feet of
 3rd plug @ ft. deep 250 or formation with 40 feet of
 4th plug @ ft. deep build solid bridge to 40' or formation with 10 feet of
 5th plug @ ft. deep or formation with feet of
 (2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER George Miller
 TD 4720 FORMATION Miss
 SURFACE PIPE 8 5/8" @ 220'
 ANHYDRITE 2150' ELEVATION 2754
 STARTING TIME & DATE 9-6-88 7:15 P.M.
 COMPLETION TIME & DATE 9-6-88 7:15 P.M.
 1st PLUG @ 2150 FT. W/ 50 SX
 2nd PLUG @ 1500 FT. W/ 75 SX
 3rd PLUG @ 240 FT. W/ 40 SX
 4th PLUG @ 40 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ 15 SX
 WATER WELL PLUGGED W/ 15 SX
 CEMENT COMPANY Allied
 TECHNICIAN D.G.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 12 1988
 09-12-1988
 INSPECTION DIVISION
 Wichita, Kansas