

1 060619

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,183 00-00
NW NE SE, SEC. 15, T 19 S, R 28 W

2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Stormont Well # 1

Operator: Palomino Petroleum

County Lane 151.78

Name & Address P. O. Box 18610

Well Total Depth 4670 feet

Wichita, KS 67218

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 8:00 am Day: 18 Month: July Year: 19 85

Plugging proposal received from John Taylor

(company name) DNB (phone) 316-687-5471

Elevation 2760

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2120

1st plug at 2120' with 50 sx cement

2nd plug at 1200' with 80 sx cement

3rd plug at 300' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Don C. Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 am Day: 18 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2120' with 50 sx cement, 2nd plug at 1200' with 80
sx cement, 3rd plug at 300' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

(If not observed) observe this plugging.

INVOICED

DATE 7-26-85

TRIV. NO. 9139

7-18

RECEIVED
STATE CORPORATION COMMISSION
07-22-1985
EJUL 22 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luttig
(TECHNICIAN)