

To: 1 090248 1-27
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION - W/2 W/2 SW, SEC. 8, T 19 S, R 28 W/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,641-00-0043 p
40' S of

Rec'd
02-22-1993

1280 feet from S section line
330 feet from W/2 section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name R. Hineman Well # 1
County Lane
Well Total Depth 4675 151.93 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 7:30 p.m. Day: 27 Month: 1 Year: 1993

Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2157'
1st plug at 2160' with 50 sx cement; 2nd plug at 1350' with 80 sx cement,
3rd plug at 675' with 50 sx cement, 4th plug at 250' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 10 p.m. Day: 27 Month: 1 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,
2nd plug at 1350' with 80 sx cement,
3rd plug at 675' with 50 sx cement,
4th plug at 250' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

~~XXXXX~~ did not observe this plugging.

INVOICED
DATE FEB 22 1993
INV. NO. 37407

Signed [Signature] (TECHNICIAN)

EFFECTIVE DATE: 11-9-92

State of Kansas

FORM MUST BE SIGNED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

101-21641-00-00

ALL BLANKS MUST BE FILLED

Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 15 92 40' ^{Spot} S W/2 W/2 SW Sec 8 Twp 19 S. Rg 28W East West

OPERATOR: License # 4767
Name: Ritchie Exploration, Inc.
Address: 125 N. Market, Suite 1000
City/State/Zip: Wichita, KS 67202
Contact Person: Rocky Milford
Phone: (316) 267-4375

1280 feet from South / North line of Section
330 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 30606
Name: Murfin Drilling Co.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: R. Hineman Well #: 1
Field Name: Wildcat
Is this a Prorated/Spaced Field? yes no
Target Formation(s): L/KC
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2774' feet MSL
Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 1300'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: none
Projected Total Depth: 4700'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
well farm pond other

Well Drilled For: Well Class: Type Equipment:
 Oil Enh Rec Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OWWO Disposal Wildcat Cable
 Seismic; # of Holes Other

If OWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Expires 5-4-93

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met.

Pusher Ed McKenna
SPUD DATE 11/19/92 INIT. RLW
LENGTH SURFACE PLANNED 200'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sects bbls. when done bbls.
RATHOLE AHEAD? Y N SIZE HOLE _____
SURFACE PIPE 8 1/2" @ 221' CONDUCTOR _____
ANHYDRITE T- B-2157 ELEVATION _____
TD 4675' FORMATION _____
RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
_____ SX _____ Y _____ N _____
Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ _____ Ft. W/ _____ SX
1 Anhydrite Base @ 7160 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1350 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 675 Ft. W/ 50 SX
4 Bottom Surface @ 250 Ft. W/ 50 SX
5 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL _____ SX (Irr. Well _____ Pond _____)
TECHNICIAN SM DATE _____ Hauling
TYPE OF CEMENT 60/40 69% 1/4 Fls sand
STARTING TIME 2:30 (AM/PM) DATE 1-27-93
COMPLETION TIME 10:00 (AM/PM) DATE 1-27-93
CEMENT COMPANY Allied