

1050237

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,981-00-00

C W/2 NW SW SEC. 8, T 19 S, R 28 W28

1980 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5104

Lease Name Hineman Well # 1

Operator: Blue Goose Drilling Co., Inc.

County _____ Lane _____

Name & Address P. O. Box 1413

Well Total Depth 4672 151.84 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 4 Month: June Year: 19 84

Plugging proposal received from Leroy Boren

(company name) Blue Goose (phone) 316-793-9222

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2120' with 50 sx cement

2nd plug at 1375' with 50 sx cement

3rd plug at 410' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Richard M. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X _____ None _____

Operations Completed: Hour: 11:45 am Day: 4 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2120' with 50 sx cement, 2nd plug at 1375' with 50

sx cement, 3rd plug at 410' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th & 7th plug to circulate rat hole

and mouse hole with 10 sx cement each.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun.

(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1984
06-07-1984
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

observe this plugging.

DATE 6-14-84

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 2010
6-14