

1 030815

JUN 14 1987

API NUMBER 15-135-23,129-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 2, T 16 S, R 21 WXX

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Sarvis Well # 1

Operator: Berexco Inc.

County Ness 139.75

Name & Address 970 Fourth Financial Center

Well Total Depth 4300 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 3 p.m. Day: 14 Month: 6 Year: 19 87

Plugging proposal received from Howard Cain

(company name) Beredco, Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1632-70'

1st plug at 1670' with 50 sx cement, 2nd plug at 910' with 100 sx cement,

3rd plug at 415' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 p.m. Day: 14 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1670' with 50 sx cement,

2nd plug at 910' with 100 sx cement,

3rd plug at 415' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1987
06-17-1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If XXX did not observe this plugging.)

DATE 6-18-87

Signed Steve Durrant (TECHNICIAN)

INV. NO. 17368

6-14

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5 25 87 month day year

API Number 15-135-23,129-00-00 East NW NW NW Sec. 2 Twp. 16 S, Rg. 21 X West 4950 Ft. from South Line of Section 4950 Ft. from East Line of Section

OPERATOR: License # 5363 Name BEREXCO INC. Address 970 Fourth Financial Center City/State/Zip Wichita, Kansas Contact Person David Munro Phone (316) 265-3311

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Ness

CONTRACTOR: License # 5147 Name BEREDCO INC. City/State Wichita, KS

Lease Name Sarvis Well # 1 Ground surface elevation 2309 feet MSL

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 50 Depth to bottom of usable water 750

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 5-8-87 Signature of Operator or Agent Max S. ... Title Geologist

Surface pipe by Alternate: 1 X Surface pipe planned to be set 350

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 12-2-87 Approved By 6-2-87

Speed 6-8-87 Set 380'

Conductor pipe required Projected Total Depth 4300 feet

Formation Mississippian

Formation Mississippian

Formation Mississippian

Formation Mississippian

Formation Mississippian

Formation Mississippian

Formation Mississippian

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug description, feet depth with, size of, and size of. Includes entries for 1st plug @ 1675-1575', 2nd plug @ 900-700', 3rd plug @ 320-370', 4th plug @ 0-40', 5th plug @, (2) Rathole with 10, and (b) Mousehole with 10.

Handwritten log: PUSHER Howard Cain - TD 4300 FORMATION MISS SURFACE PIPE 8 7/8 @ 385 ANHYDRITE 1632 ELEVATION 2314 STARTING TIME & DATE 3:00 PM COMPLETION TIME & DATE 5:50 PM 1st PLUG @ 1670 FT. W/ 50 SX 2nd PLUG @ 910 FT. W/ 100 SX 3rd PLUG @ 415 FT. W/ 40 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ Hard SX CEMENT COMPANY B.S.T. form 6/4 606 eyed TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION JUN 17 1987 06-17-1987 CONSERVATION DIVISION Wichita, Kansas

No witness