

To: 1 090191 4-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,638-00-00
S/2 SW NE, SEC. 9, T 16 S, R 21 W/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 8996

Operator: Mid Continent Resources, Inc.
Name & Address P.O. Box 399
Garden City, KS 67846

2970 feet from S section line
1980 feet from E section line

Lease Name Lamer Well # 1-9

County Ness

Well Total Depth 4365 141.86 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 506, Russell, KS 67665

Company to plug at: Hour: 3 a.m. Day: 29 Month: 4 Year: 19 92

Plugging proposal received from Tom

(company name) Emphasis (phone) 913-483-5345

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1642-80'
1st plug at 1680' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,
3rd plug at 500' with 50 sx cement, 4th plug at 230' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 a.m. Day: 29 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1680' with 50 sx cement,
2nd plug at 1000' with 80 sx cement, 3rd plug at 500' with 50 sx cement,
4th plug at 230' with 50 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(if additional description is necessary, use BACK of this form)

I (CRK) / did not observe this plugging.

INVOICED
DATE 5-6-92
INV. NO. 35164

Signed [Signature]
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
MAY 7 1992
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 12-16-91

DISTRICT #

SEA? Yes No

State of Kansas 15
NOTICE OF INTENTION TO DRILL 135-23,638-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 12 29 91
month day year

Spot C S/2 SW NE Sec 9 Twp 16 S Rg 21 East West

OPERATOR: License # 8996
Name: Mid Continent Resources, Inc.
Address P.O. Box 399
City/State/Zip: Garden City, KS 67846
Contact Person: Scott Corsair
Phone: 913-398-2270

2970 feet from South / North line of Section 1980
1980 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Ness

CONTRACTOR: License #: 30606
Name: ~~Murfin Drilling Company~~
Emphasis Drilling

Lease Name: Lamer Well #: 1-9
Field Name: Wildcat

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Cherokee

Nearest lease or unit boundary: 1980
Ground Surface Elevation: 2310 est feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext Air Rotary
OWWO Disposal X Wildcat Cable
Seismic: # of Holes Other

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 130
Depth to bottom of usable water: 1000

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 250'

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Length of Conductor pipe required: NA
Projected Total Depth: 4360

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
well X farm pond other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

DWR Permit #:
Will Cores Be Taken? yes X no

If yes, proposed zone: 200' Alt. II Req.

Exp. 6/11/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

1. Notify the appropriate district office prior to completion of well

638

Pusher Tom INIT. SM

SPUD DATE 4-21-92 INIT. SM

LENGTH SURFACE PLANNED 200

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 215 CONDUCTOR
ANHYDRITE T- 1/2" B- 1680 ELEVATION

TD 4365 FORMATION MISS.

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

1 Anhydrite Base @ 1680 Ft. W/ 50 SX

2 1/2 Base Anhyd. @ 1000 Ft. W/ 80 SX

3 1/2, 1/2 Plug @ 500 Ft. W/ 50 SX

4 Bottom Surface @ 230 Ft. W/ 50 SX

40' Plug @ 10 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/10 SX

WATER WELL NO SX (Irr. Well Pond Hauling)

TECHNICIAN SM DATE 4-28-92

TYPE OPERATION CONSTRUCTION DATE 4-28-92

STARTING TIME 6:40 DATE 4-28-92

COMPLETION TIME 5:30 (AM/PM) DATE 4-29-92

CEMENT 17 1/2' Benton

RECEIVED
MAY 1 1992
WICHITA COUNTY COMMISSION
DATE 4-29-92