

1 050546

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 150'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,829 -00-00 **R**

N of SE, <sup>NE SE</sup> SEC. 9, T 16 S, R 21 **(W/E)**

1800 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Lamer Well # 1-B

Operator: Pickrell Drilling Company

County Ness 140.73

Name & Address 110 N. Market, Suite 205

Well Total Depth 4330 Mississippi feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 265'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling Company License Number 5123

Address 110 N. Market, Suite 205 Wichita Kansas 67202

Company to plug at: Hour: 7:30 Am Day: 4 Month: June Year: 19 85

Plugging proposal received from Gary Christopher

(company name) Pickrell Drilling Company (phone) 316-262-8427

work: Keep Hole full of good heavy drilling mud and spot all plugs through open ended drill pipe. 1st plug at 1660' with 50 sacks of cement. 2nd plug at 820' with 70 sacks of cement. 3rd plug at 300' with 40 sacks of cement. 4th plug at 40' with a solid bridge built of 1 sack of hulls and a 8 5/8" wiper plug and 10 sacks of cement to the surface. Circulate the rat hole with 15 sacks of cement. Use 60/40 pozmix 2% gel 3% cc for cement

Anhydrite top was 1650' Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:30 am Day: 4 Month: June Year: 19 85

ACTUAL PLUGGING REPORT Kept Hole full of good heavy drilling mud and spot all plugs through open ended drill pipe. 1st plug at 1660' with 50 sacks of cement. 2nd plug at 820' with 70 sacks of cement. 3rd plug at 300' with 40 sacks of cement. 4th plug at 40' with a solid bridge built of 1 sack of hulls and a 8 5/8" wiper plug and 10 sacks of cement to the surface. Circulated the rat hole with 15 sacks of cement. Used 60/40 pozmix 2% gel 3% cc cement pumped by Allied cementing.

Remarks: (if additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
06-07-1985  
JUN 07 1985

(XXX old dot) observe this plugging.

INVOICED

DATE 6-18-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 8556