

1 120873

1-14

API NUMBER 15- 135-01,015-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW SE, SEC. 9, T 16 S, R 21 W/X  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8996

Lease Name Lamer Well # 2-9 OWWO

Operator: Mid Continent Resources, Inc.

County Ness

Name & Address P.O. Box 399

Well Total Depth 4345 141.21 feet

Garden City, KS 67846

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 199.9

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number 5287

Address Ness City, KS 67560

Company to plug at: Hour: 9 a.m. Day: 14 Month: 1 Year: 19 94

Plugging proposal received from Dean Ives

(company name) Mid Continent Resources, Inc. (phone) 913-398-2270

vers: 4 1/2" at 4340' w/125 sx cement, PBTD 4287', Perfs at 4200-08'

1st plug sand back to 4150' and dump 4 sx cement on top of sand through bailer,

2nd plug at 1550' with 50 sx cement,

3rd plug at 1000' with 80 sx cement,

4th plug at 230' with 40 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 14 Month: 1 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 50 sx cement at 1550',

3rd plug pumped 80 sx cement at 1000',

4th plug pumped 40 sx cement at 230',

5th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE FEB 04 1994

Signed Dean Rankin (TECHNICIAN)

INV. NO. 39853

RECEIVED STATE CORPORATION COMMISSION JAN 20 1994 01-20-1994 CONSERVATION DIVISION Wichita, Kansas