

1090394

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,995 - 00-00

C SW SW , SEC. 16 , T 16 S, R 21 W/E

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Irvin Well # 1

Operator: Berexco, Inc.

County Ness 140.73

Name & Address 970 Fourth Financial Center

Well Total Depth 4330 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 26 Month: January Year: 1986

Plugging proposal received from Howard Cain

(company name) Beredco (phone) 316-265-2856

Elevation 2342

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1639-79'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 900' with 50 sx cement

3rd plug at 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 am Day: 26 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1665' with 50 sx cement, 2nd plug at 900' with 50 sx

cement, 3rd plug at 400' with 50 sx cement, 4th & 5th plugs - solid bridge -- hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

JAN 30 1986
01-30-1984
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan.

(If additional description is necessary, use BACK of this form.)

INVOLCED

(If not) observe this plugging.

DATE JAN 31 1986

Signed Robert B. Tarbutton
(TECHNICIAN)

INV. NO. 12206

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 25 86 month day year

API Number 15-135-22,995-00-00

OPERATOR: License # 5363 Name BEREXCO INC Address 970 Fourth Financial Center City/State/Zip Wichita, KS 67202 Contact Person Don Beauchamp Phone (316)265-3311

Sec. 16 SW SW Sec. 16 Twp. 16 S. Rg. 21 E. 660 Ft. from South Line of Section 4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5147 Name Beredge, Inc City/State Wichita, KS

Nearest lease or unit boundary line 660 feet County Ness

Lease Name Levin Well 1 Ground surface elevation 2342 feet MSL

Well Drilled For: Oil SWD Infield Mud Rotary Gas Inj Pool Est Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Surface pipe by Alternate: 1 2 X

If OWWO: old well info as follows:

Depth to bottom of fresh water 27

Depth to bottom of usable water 712

Surface pipe planned to be set 350

Projected Total Depth 4350 feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Alternative cementing will be done immediately upon setting production casing. Date 1-2-86 Signature of Operator or Agent Kevin Jones Title Geologist

For KCC Use:

Conductor Pipe Required feet: Minimum Surface Pipe Required feet: Per Alt. X (2) 3

This Authorization Expires 7-8-86 Approved By 1-8-86

Kevin Jones SP 371' 1-21-86

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 1750 feet depth with 50 sxs of 60/40 pozmix .6% gel. 2nd plug @ 900' feet depth with 50 sxs of 3rd plug @ 380 feet depth with 50 sxs of 4th plug @ 40 feet depth with 50 sxs of 5th plug @ 15 feet depth with 10 sxs of

(2) Rathole with 15 sxs (b) Mousehole with 10 sxs

PUSHER Howard Cainc TD 4900 FORMATION Miss SURFACE PIPE 8 5/8 @ 371 ANHYDRITE 1639 ELEVATION STARTING TIME & DATE COMPLETION TIME & DATE 3:00pm 1st PLUG @ 1665 FT. W/ 50 SX 2nd PLUG @ 900 FT. W/ 50 SX 3rd PLUG @ 400 FT. W/ 50 SX 4th PLUG @ 40 FT. W/ 50 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Sen TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION JAN 30 1986 CONSERVATION DIVISION 01-30-1986