

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,314-00-00 ²³³⁹⁴ ^{AUG 88}

LEASE NAME GIESS

WELL NUMBER 1

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 30 TWP. 16 RGE. 24 ~~XX~~ or (W)

COUNTY Ness

Date Well Completed November 2, 1989

Plugging Commenced October 26, 1989

Plugging Completed November 2, 1989

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lee Phillips Oil Company

ADDRESS 125 N. Market, Suite 1532, Wichita, KS 67202

PHONE# (316) 264-6392 OPERATORS LICENSE NO. 5215

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-2-89 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		314'	0'	8-5/8"	314'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged hole with 205 sacks, 60/40 Pozmix, 6% gel as follows: 50 sx @ 1950', 80 sx @ 1150', 40 sx @ 345', 10 sx @ 40' to surface, 15 sx R.H., 10 sx M.H. P.D. @ 3:30 p.m. 11-2-89.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P.O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING Lee Phillips Oil Company

STATE OF Kansas COUNTY OF Seawick ^{13 1990} ⁰²⁻¹³⁻¹⁹⁹⁰ ^{ss.}

Lee E. Phillips III

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed; that the same are true and correct, so help me God.


(Signature) Lee E. Phillips III

(Address) 125 No. Market, Suite 1532, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 89

Alice M. Oaks
Notary Public

My Commission Expires: _____



MALLARD JV, INC.
P.O. BOX 1009
McPHERSON, KS 67460

ORIGINAL

DRILLERS' LOG

OPERATOR: Lee Phillips Oil Company
125 N. Market, Suite 1532
Wichita, KS 67202

WELL: Giess #1

API#: 15-135-23,394-00-00

COMMENCED: October 26, 1989

LOCATION: SE SW SE

COMPLETED: November 2, 1989

330 Ft. FSL, 1650 Ft. FEL

TOTAL DEPTH: 4600 Ft.

SEC. 30 TWP. 16 S RGE. 24 W

ELEVATION: 2542 Ft. G.L.

COUNTY: Ness

2550 Ft. K.B.

Cut 12 1/4" hole to 316' and ran 8 joints 8-5/8" x 28# x 308.93' surface casing. Set at 314' with 220 sacks 60/40 Pozmix, 2% gel, 3% cc. Cement did circulate. P.D. @ 5:45 p.m. 10-26-89.

Drilled 7-7/8" hole to 4600' R.T.D. Mississippi formation, ran electric log, and plugged with 205 sacks 60/40 Pozmix, 6% gel as follows:

- 50 sx @ 1950'
- 80 sx @ 1150'
- 40 sx @ 345'
- 10 sx @ 40' to surface
- 15 sx R.H., 10 sx M.H.
- P.D. @ 3:30 p.m. 11-2-89

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1990
02-13-1990
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF MCPHERSON) SS:

I, Dick Hess of MALLARD JV, INC. hereby certify that this is a true and correct copy of the log of the Giess #1 well as reflected by the files of Mallard JV, Inc.

Dick Hess
Dick Hess

Subscribed and sworn to before me this 8th day of November, 1989.

5-26-93
My Appt. Exp.



Bryan K. Hess
NOTARY PUBLIC