

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,641-00-00

LEASE NAME Marhofer

WELL NUMBER 1

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 30 TWP. 16 RGE. 24 ~~XX~~ or (W)

COUNTY Ness

Date Well Completed 1/18/92

Plugging Commenced 1/18/92

Plugging Completed 1/18/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lee Phillips Oil Company

ADDRESS 125 N. Market, #1532, Wichita, KS 67202

PHONE# (316) 264-6392 OPERATORS LICENSE NO. 5215

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/17/92 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4600 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From 343'	To 0'	Size 8-5/8"	Put in 343'	Pulled out None

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1992
03-235-1992

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Plugged with 265 sacks 60/40 Pozmix, 6% gel, 1/4# floeal per sack as follows: 50 SX @ 1920', 80 sacks @ 1050', 50 SX @ 600', 50 SX @ 350', 10 SX @ 40', 15 SX rathole, 10 SX mousehole. PD 12:45 a.m. 1/18/92.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Phillips Oil Company


STATE OF Kansas COUNTY OF Sedgwick, ss.

Lee E. Phillips, III, owner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Lee E. Phillips III

(Address) 125 No. Market - Suite 1532 Wichita, KS

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 92



Alice M. Oaks
Notary Public

My Commission Expires: May 10, 1992.