

State of Kansas



15-135-20157-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drlg. Co.

Complete Address: 705 4th Nat'l Bldg., Wichita, Ks.

Lease Name: Dubbs "E" Well No. 2

Location: C SE SW Sec. 26 Twp. 16 Rge. 24 (E)(W) X

County: Ness Total Depth 4530 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 900' and displace  
70 sf cement thru drill pipe. Heavy mud to 270' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of ceklar. Plug rat hole  
with 2 sc cement.

RECEIVED

STATE CORPORATION COMMISSION

JUL 1 1968 Very truly yours,

CONSERVATION DIVISION  
Wichita, Kansas

07-01-1968

Leo F. Massey  
Conservation Division Agent