



15-135-20183-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas

09-12-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Miller of Graves Drlg. has this  
date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: John C. Graves, Et al

Complete Address: 505 Union Center Wichita, Ks.

Lease Name: Wymam Well No. 1

Location: App. C SE NW Sec. 4 Twp. 16 Rge. 22 (E)(W) X

County: Ness Total Depth 4425 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Miller was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Leo J. Massey  
Conservation Division Agent