

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-23,381-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Bankoff Oil Company OPERATOR'S LICENSE NO. 6040

ADDRESS 100 S. Market, Suite 203A, Wichita, KS 67202 PHONE # (316) 262-2784

LEASE (FARM) Wyman WELL NO. 1 WELL LOCATION NE SW SW COUNTY Ness

SEC. 19 TWP. 16S RGE. 21 ~~(E) or (W)~~ TOTAL DEPTH 4340' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 260' CEMENTED WITH 170 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud 20 minutes, 1st plug at 1640'-50 sx.

2nd plug at 900'-80 sx. and 2 sx of hulls. 3rd plug at 300'-40 sx. 4th plug at 40' SB-10

sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 7:45 p.m. on 9-16-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wilmer Dreiling PHONE # (913) 726-4850

ADDRESS 408 Jefferson, Ellis, KS .67637

PLUGGING CONTRACTOR Abercrombie drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS .67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack W. Wharton
(Operator or Agent)

DATE: 10-17-89

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1989
CONSERVATION DIVISION
Wichita, Kansas