

15-135-20081-00-00

Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 15 Twp. 16S Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines C NW SW
Lease Owner O. A. Sutton
Lease Name Elmore Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 23 1967
Application for plugging filed June 12 1968
Application for plugging approved June 13 1968
Plugging commenced July 5 1968
Plugging completed July 5 1968
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4275 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	
				5 1/2"	4276'	2339'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 3700', sand up to 3675', dumped 5 sacks cement.
Top plug put in by Halliburton, 25 sacks of gel, 5 sacks hulls & 140 sacks Pozmix. Job complete 7-5-68.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1968
CONSERVATION DIVISION
Wichita, Kansas

07-16-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.
Address 320 North Park, Stafford, Kansas (Permit #490)


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
800 Sutton Place, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of July, 1968.

Jean S. Taylor
Notary Public.

My commission expires June 28, 1970.



DRILLER'S LOG

15-135-20081-00-00

COMPANY:

O. A. SUTTON
800 SUTTON PLACE
WICHITA, KANSAS 67202

WELL NAME:

ELMORE #1
C NW SW SEC. 15-16S-21W
NESS COUNTY, KANSAS

CONTRACTOR:

WALTERS DRILLING CO.
400 INSURANCE BUILDING
WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED:
ROTARY DRILLING COMPLETED:

NOVEMBER 10, 1967
NOVEMBER 23, 1967

ELEVATION:

2334 KB

CASING RECORD:

8 5/8" set @ 250' w/ 160 sx. cement

LOG

0 - 40	Surface Clay and Post Rock
40 - 300	Shale
300 - 1170	Shale, Shells and Sand
1170 - 1305	Sand
1305 - 1626	Shale
1626 - 1672	Anhydrite
1672 - 2436	Shale
2436 - 2684	Lime and Shale
2684 - 2750	Lime
2750 - 2925	Lime and Shale
2925 - 3060	Shale and Lime
3060 - 3230	Lime and Shale
3230 - 3550	Shale
3550 - 3865	Lime and Shale
3865 - 3998	Lime
3998 - 4110	Lime and Shale
4110 - 4188	Lime
4188 - 4211	Sand and Shale
4211 - 4245	Lime and Sand
4245 - 4275	Lime and Chert
<u>4275</u>	<u>Rotary Total Depth</u>

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1968
CONSERVATION DIVISION
Wichita, Kansas

06-13-1968

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY

ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
this 12th day of December, 1967.

JUANITA M. GREEN, Notary Public
My Commission Expires: October 1, 1971