

15-135-20088-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 15 Twp. 16S Rge. 21 (X) (W)

Location as "NE/CNW/SW" or footage from lines 135' No. of C NE NW
Lease Owner Walters Drilling Co. & McClure Oil Company
Lease Name Schwartzkopf Well No. 1
Office Address 400 Insurance Building - Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-3-67 19
Application for plugging filed 12-3-67 19
Application for plugging approved 12-3-67 19
Plugging commenced 12-3-67 19
Plugging completed 12-3-67 19



Locate well correctly on above Section Plat

Reason for abandonment of well or producing formation commercial quantities of oil not found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 247' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 800' w/ 100 sacks cement
2nd plug @ 240' w/ 25 sacks cement
Top Plug @ 40' w/ 10 sacks cement


RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1967
12-11-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.
Address 400 Insurance Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Donald D. Keller (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D Keller
400 Insurance Bldg., Wichita, Kansas 67202 (Address)



Subscribed and sworn to before me this 11th day of December, 1967
Juanita M. Green Notary Public

15-135-20088-00-00

DRILLER'S LOG

COMPANY: WALTERS DRILLING CO. & MC CLURE OIL CO.
 400 INSURANCE BUILDING
 WICHITA, KANSAS 67202

WELL NAME: SCHWARTZKOPF #1
 135' No. of C NE NW
 SECTION 15-16S-21W
 NESS COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
 400 INSURANCE BUILDING
 WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED: NOVEMBER 24, 1967
 ROTARY DRILLING COMPLETED: DECEMBER 3, 1967

ELEVATION: 2297 KB

CASING RECORD: 8 5/8" @ 247' w/ 160 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1967

12-11-1967

CONSERVATION DIVISION
Wichita, Kansas

LOG

| | |
|-------------|---------------------------------------|
| 0 - 248 | Surface Clay and Shale |
| 248 - 1005 | Shale - Sand Streaks |
| 1005 - 1265 | Dakota Sand |
| 1265 - 1330 | R. B. Streaks of Sand |
| 1330 - 1600 | Sand and Shale |
| 1600 - 1635 | Anhydrite |
| 1635 - 1735 | Shale |
| 1735 - 2085 | Shale w/ Lime |
| 2085 - 2475 | Shale |
| 2475 - 2575 | Lime - Shale |
| 2575 - 2703 | Lime |
| 2703 - 2850 | Lime and Shale |
| 2850 - 3028 | Shale and Lime |
| 3028 - 3210 | Lime and Shale |
| 3210 - 3675 | Shale and Lime |
| 3675 - 4085 | Lime |
| 4085 - 4125 | Lime Sandy |
| 4125 - 4168 | Sand and Shale |
| 4168 - 4187 | Shale |
| 4187 - 4230 | Sand, Lime and Chert |
| 4230 - 4250 | Lime, Sand and Chert |
| <u>4250</u> | <u>Rotary Total Depth - D & A</u> |

The undersigned, Donald D. Keller, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY Donald D. Keller
DONALD D. KELLER, Office Manager

Subscribed and sworn to before me
this 11th day of December, 1967.

Juanita M. Green
 Juanita M. Green, Notary Public

My Commission Expires:
 October 4, 1971