


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 12 Twp. 16 Rge. 21 (E) (W)
Location as "NE/CNW/SW" or footage from lines 1980' from South line
Lease Owner Cabot Corporation 1980' from E1
Lease Name Elmore Ryan Well No. 1
Office Address Box 1101, Pampa, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-19-64 19
Application for plugging filed 6-19-64 19
Application for plugging approved 6-19-64 19
Plugging commenced 6-19-64 19
Plugging completed 6-19-64 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4305 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	318'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 600' Plug 20 sks. cement through the drill pipe
Mud to 300' Plug 10 sks. cement through the drill pipe
Mud to 40' Plug 1/4 sk. hulls 10 sks. cement to base of cellar
Job completed @ 9:00 p.m. 6-19-64

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1964

06-23-1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 1964

My commission expires April 1, 1967

Ulanda Nichols
Ulanda Nichols Notary Public.

15-135-00344-00-00

DRILLER'S LOG

COMPANY: Cabot Corporation
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: ELMORE RYAN #1
 LOCATION: 1980' from South line
 1980' from East line
 Sec. 12-16-21, NESS COUNTY, KANSAS
 COMMENCED: 6-8-64
 COMPLETED: 6-19-64

0	40	Post Rock
40	318	Shale & Lime Streaks
318	900	Shale
900	920	Redbed
920	1060	Shale & Sand
1060	1325	Sand
1325	1606	Redbed & Shale
1606	1646	Anhydrite
1646	2310	Shale & Shells
2310	2526	Shale & Lime
2526	2850	Lime
2850	2960	Lime & Shale
2960	3180	Lime
3180	3326	Lime & Shale
3326	3390	Lime
3390	3530	Lime & Shale
3530	4225	Lime
4225	4275	Conglomerate
4275	4305	Mississippi Chert
	<u>4305</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1964
06-23-1964
CONSERVATION DIVISION
Wichita, Kansas


Set 8 5/8" J-55 new 24# surface casing @ 318' with landing joint cemented with 100 sacks Posmix with 2% c.c. and 100 sacks Regular with 2% c.c.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Elmore Ryan #1 well, located 1980' from South line and 1980' from East line of Section 12, Township 16, Range 21, Ness County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 22nd day of June, 1964.



Ulanda Nichols

My Commission Expires
April 1, 1967